



**NOTES:**

1. ANCHOR RODS SHALL BE INSTALLED FOLLOWING STRICT RECOMMENDATIONS AND PROCEDURES OF MANUFACTURER.
2. CONTRACTOR SHALL TAKE CAUTION NOT TO DRILL ANCHOR THROUGH ANY REINFORCING REBAR DURING INSTALLATION.
3. ANCHOR RODS AND STEEL ANGLE SHALL BE GALVANIZED OR STAINLESS STEEL.
4. ANCHOR RODS SHALL BE LOCATED A MINIMUM OF 4" (102mm) FROM ANY CONCRETE EDGE OR COLD JOINT.
5. ANCHOR RODS SHALL BE INSTALLED A MINIMUM OF 3" (76mm) AWAY FROM ICF WEBS.
6. SUPPORTED BRICK VENEER HEIGHT SHALL NOT EXCEED 20' (6.1m).

# 6" R30 AMVIC™ ICF WALL WITH BRICK SHELF ANGLE AT GRADE



28 December 2023