

BRICK TIE SIZE AND SPACING AS SPECIFIED, INSTALLED PRIOR TO CONCRETE PLACEMENT

MORTAR DROPPING COLLECTION DEVICE WITH INTEGRATED INSECT BARRIER

FILL CAVITY WITH SPRAY FOAM INSULATION

METAL FLASHING WITH DRIP EDGE

SEALANT AND BACKER ROD

WEATHER RESISTIVE BARRIER

HORIZONTAL AND VERTICAL REINFORCEMENT AS PER STRUCTURAL DESIGN

CUT SAW KERF AND SECURE FLASHING WITH SEALANT

#4 (10M) BAR 16" (406mm) LONG [6x10" (152x254mm)] @ 6' (1.8m) O.C.

THERMALLY BROKEN SHELF ANGLE SUPPORT SYSTEM WITH ANCHOR BOLT AS SPECIFIED

NOTCH PRECAST AND GROUT LOCALLY

CONCRETE TOPPING

PRECAST CONCRETE SLAB

DRYPACK VOID PRIOR TO BUILDING WALL ABOVE

8" (203mm) R22 AMVIC ICF

1/2" (13mm) GYPSUM BOARD

8" R22 AMVIC™ ICF WITH PRECAST CONCRETE TRANSVERSE SECTION

Alleguard
1(877) 470-9991 alleguard.com